



10641 HIGHWAY 36
COVINGTON, GEORGIA
30014
t 770.786.3031
f 770.786.3046

Newton County Water & Sewage Authority - Addition

Division 22 - Plumbing

Plumbing

Todd Young Plumbing	\$129,400.00
Matt Davis Plumbing Company	\$163,200.00
McLeroy Plumbing Service	<i>No Bid</i>
King's Plumbing Company	<i>No Bid</i>

Todd Young Plumbing
1137 Brett Drive
Conyers, GA 30094

Quote

Date

6/16/2026

Number

4326

Name

SUNBELT BUILDERS

Job / Address

NCWSA Office Addition

Qty	Description	Total
8	WC-1 Kohler Kingston K-4325 Sloan 111-ESS-1.28	
8	LAV-1 Kohler K-2032 Sloan EAF-100-PLG-CP-0	
2	UR-1 Kohler Bardon K-4904-ET Sloan 186 ESS-0	
4	FCO Watts CO-260	
1	WCO	
7	FD Watts FD-300-5 Watts FD-100-A w/ Trap Seal	
1	WH-1 Prier C-634BX1	
1	SK-1 Elkay ELUH361710DBG Elkay LKGT1041	
1	EWB-1 AO Smith ENL-30 -SHELF TO BE PROVIDED AND INSTALLED BY OTHERS	
1	HWRP	
2	CO	
3	RD-1 MIFAB R1100	
Quote is good for 30 Days from date.		Total

Signature

Todd Young Plumbing
1137 Brett Drive
Conyers, GA 30094

Quote

Date
6/16/2026

Number
4326

Name
SUNBELT BUILDERS

Job / Address
NCWSA Office Addition

Qty	Description	Total
1	Tie plumbing into existing Water Heater	
1	Total Cost for the Job	129,400.00
Quote is good for 30 Days from date.		Total \$129,400.00

This Quote does not include the sinks themselves. If you would like for us to include sinks in our quote please request it with our office.

We do not provide or install roof boots for our vent pipes. These

Signature _____

Matt Davis Plumbing Company, Inc.
P.O. Box 230
Covington, GA 30015
678-625-1050

Estimate

Date	Estimate #
6/16/2026	7080

Name / Address
Sunbelt Builders, Inc. 10641 Hwy. 36 Covington, GA 30014

		Project	
		NCWSA ADDITION	
Description	Qty	Rate	Total
H/C TOILETS	8		
H/C URINALS	2		
H/C LAVATORIES	8		
WATER HEATER	1		
RECIRC PUMP	1		
FLOOR DRAINS	5		
FLOOR CLEANOUTS	3		
INSULATION	1		
BREAK SINK	1		
WALL HYDRANT	1		
ROOF DRAINS	3		
PARAPET DRAINS	4		
4" PVC STORM PIPE CONNECTION TO CIVIL	1		
3" COPPER w/ RISER @ ENTRANCE	1		
SAWCUT & REMOVAL	1		
TOTAL ESTIMATE		163,200.00	163,200.00
**** NOTES ****			
A) DWV PIPING IS PVC BELOW GRADE / NO-HUB ABOVE			
B) WATER PIPING IS L COPPER			
C) INSULATION IS 1" FG ASJ			
THANKS FOR YOUR CONSIDERING MATT DAVIS PLUMBING FOR THIS PROJECT		Total	\$163,200.00